8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

| Description of work. | Unit of work. | Rate per unit. |
|---|---|---|
| Clearing site etc. ... ... ... ... | Lump sum. Rs. | |
| Earthwork excavation ... ... ... ... | C. yd. | 525 |
| Earthwork, filling basement, watering and tamping .. | C. yd. | 537 |
| Burnt stone in mortar with bond slabs foundation .. | C. ft. | 13,521 |
| Do sized do do basement .. | C. ft. | 6,413 |
| Burnt brick in mortar superstructure ... .. | C. ft. | 18,608 |
| Do arch work (including centring) ... .. | C. ft. | 2,039 |
| Burnt stone slabs, 4″ to 6″ thick, finely dressed ... .. | S. ft. | 2,077 |
| Parapet walls including pedestals with plastering etc. .. | R. ft. | 338 |
| Masonry scrolls with plaster etc., on verandah parapets .. | No. | 8 |
| Teakwood work wrought and put up, complete ... | C. ft. | 1,166·67 |
| Roofing with 1st class Mangalore tiles, teak reepers, ridge tiles, set in mortar. | Sqr. | 93·08 |
| Ornamental finials ... .. .. .. | No. | 8 |
| Pukka terrace with brick on edges ... ... | Sqr. | 29·51 |
| Ornamental dental cornice ... ... .. | R. ft. | 246 |
| Ornamental thin dental cornice ... ... .. | R. ft. | 318 |
| Moulding or strong courses .. ... .. | R. ft. | 1,270 |
| Mock doors in mouldings to be made in side blocks ... | No. | 4 |
| Teakwood eave boards with painting etc., complete ... | R. ft. | 436 |
| Pointing with mortar ... ... ... .. | Sqr. | 17·55 |
| Plastering with mortar .. .. .. | Sqr. | 370·48 |
| White and color washing ... .. ... | Sqr. | 370·48 |
| Flooring with Cadappah stone slabs, 1½″ to 2″ thick, cement or asphalt pointing. | Sqr. | 76·53 |
| Concrete work 2″ thick under floor slabs, watering and tamping. | C. ft. | 1,275 |
| Teakwood exterior doors panelled, approved hinges, bolts, locks etc., complete. | S. ft. | 600 |
| Teakwood interior doors ½ panelled and ½ glazed, approved hinges etc. | S. ft. | 428 |
| Teakwood window outside panelled, inside glazed with iron bars and approved hinges. | S. ft. | 775 |
| Teakwood glazed oval windows and ventilators and iron bars. | S. ft. | 273 |
| Teakwood almirahs with battened shutters and partition, plank, hinges, locks, complete. | S. ft. | 200 |
| Painting to doors and windows etc., two fine coats .. | Sqr. | 45·12 |
| Wood-oiling to wood work .. ... ... | Sqr. | 123·00 |
| Tarring portion of wood work embedded in walls ... | Sqr. | 20·00 |
| Zinc gutters to the valleys ... .. .. | R. ft. | 240 |
| Teakwood screens with a door in the centre, complete ... | S. ft. | 397 |
| Iron works to trusses .. ... ... ... | No. | 15 |
| Iron diagonal trusses for 20 × 20 feet hall with all charges and fixing etc. | No. | 6 |
| Cast iron pillars for hall 9″ thick, 9½′ high (10′ high with capitals) including all charges and fixing etc. | No. | 8 |
| Forming approach road etc. .. ... ... | Lump sum Rs. | |

K. PRAHLADA RAO,
*Executive Engineer.*

## MYSORE LOCAL SERVICE AND PLEADERS' EXAMINATIONS, 1902.

*Notification No.* 213—*E, dated Bangalore, 7th April* 1902.

Candidates for the ensuing Revenue, Excise, Registration and Forest Examinations are informed that they will be examined in the new Regulations and Rules now in force and not in the repealed ones.

V. A. RAJARATNA MUDALIAR,
*Secy. to the Board of Examiners.*

## AMRUT MAHAL DEPARTMENT.

SALE OF BULLOCKS AT SANTEMARAHALLI MARKET, CHAMRAJNAGAR TALUK.

*Dated 12th April* 1902.

With reference to notification, dated 7th October 1901, published in the *Mysore Gazette*, the public are hereby informed that the sales on the last market day in each month are stopped until further notice.

H. NANJUNDARAJ URS, *Superintendent.*